

BRIHANMUMBAI MUNICIPAL CORPORATION
MUMBAI FIRE BRIGADE

Sub: Provisional Fire Safety Approval for the construction of additional two stretcher lifts in the existing Low-Rise College building No. 01 on plot bearing C.T.S. No. 128A/1 & 128-A(Pt), of Village Chembur for M/s. Vivekanand Education Society.

Ref: Online file submitted by Architect B. H. Wadhwa of M/s. B. H. Wadhwa & Co. for the Owner, M/s. Vivekanand Education Society u/r. File No. P-24534/2024/(128 A/1 and 128 A Part)/M/E Ward/CHEMBUR-E-CFO/1/New.

OWNER M/S. VIVEKANAND EDUCATION SOCIETY.

This is an existing low rise institutional building No. 1, having composite two wings i.e. C-1 & C-2 each comprising of ground plus upper five floors having brick walled, R.C.C. framed, partly flat & partly slopping roof structure for educational activities (VES College). The party is holding full occupation certificate to occupy & use ground floor to 5th upper floors from E.E.B.P.(E.S.) u/No. CE/3105/BPES/AM, dated 10/04/2008.

Further, this department had issued Provisional Fire Safety Approval vide File No. CE/3105/BPES/AM-CFO/1/New, dated 15/06/2024 regarding the fire safety measures for the addition & alteration in the complete bldg. No. 01 of the said Swami Vivekanand College (However its Final approval not obtained).

Now, Architect has uploaded plans & requesting this department to issue fire-protection & fire-fighting requirements for the proposed construction of two stretcher lifts with lobby from ground to 5th upper floor & lift machine rooms on the terrace as shown on the plans. This is Low-Rise College Building comprising of two wings i.e. C1 & C2 wings. Both wings are having ground floor + 1st to 5th upper floors with a total height of 21.64 mtrs. from general ground level up to terrace level. Both wings are connecting to each other at each floor level by 02.44 mtrs. wide common passage, bldg. is having four existing open type staircases & four passenger lifts as shown on plans.

The Architect has uploaded structural stability certificated issued by Structural Engineer, Mr. B. H. Wadhwa of M/s. B. H. Wadhwa & Co. having License No. STR - 840004080, dated 16/12/2024.

In view of the above, as far as this department is concerned this Provisional Fire Safety Approval is issued from fire safety point of view for the proposed construction of additional two stretcher lifts with lobby from ground to 5th upper floors & lift machine rooms on the terrace in the existing collage building No. 01 as per details shown on the uploaded plans, signed in token of approval, subject to satisfactory compliance with the following fire safety requirements.

It is the responsibility of the owner/occupier to take compliance with the following fire safety requirements from CFO's Dept. before actual commencement of the activity. The Concerned department shall ensure that activity does not commence till the Final Fire Safety Approval of this department is issued.

- 1) All the earlier fire safety requirements stipulated by CFO's dept. vide Provisional Fire Safety Approval vide File No. CE/3105/BPES/AM-CFO/1/New, dated 15/06/2024, shall be strictly adhered to along with following additional fire safety requirements;

- 2) Original frame work of the structure & elements of the structure i.e. beams, columns, load bearing walls, floors etc. should not be disturbed by chipping, tampering etc.
- 3) Internal layout and construction, additions & alteration and extension shall be strictly in accordance with the details shown on the enclosed plans. The original entrances, exits, passages as per the initial approved plans shall not be changed or altered.
- 4) The entrance, common corridor/passages/lift lobby, means of escape shall be kept free from obstructions, encroachments, storages etc. & common passage of both the wings shall be kept & maintained throughout the premises on all floors to have easy means of escape in the event of an emergency.
- 5) Wherever timber, plywood etc. used on site will be treated/painted with fire retardant paint.
- 6) False ceiling, suspenders/runners shall be of non-combustible materials.
- 7) No loft shall be constructed on the premises.
- 8) The electrical wiring shall be non-toxic, non-flammable and low smoke having copper core & shall be laid in metal conduit pipe continuously bonded to earth
- 9) Electric wiring shall be of copper core, cables & E.L.C.B./M.C.B. shall be incorporated in the electrical installations of B.S.I. mark.
- 10) The main door of the electric meter room shall be outside the bldg. premises & should not open in the staircase block.
- 11) Electric circuits of all the internal passage lighting & fire-fighting systems shall be provided with an independent alternate power supply connection from inverter of sufficient capacity.
- 12) Electric wiring/installations shall be as per the prevailing Electricity Act & Rules & the Test Certificate from the authorized Contractor shall be produced while obtaining compliance of the above said work.
- 13) Entire premises shall have provision or provided with openable windows, so as to have sufficient ventilation in case of an emergency.
- 14) Entrance/exit doors & doors to the common corridors shall be provided, as per location shown in the plan and shall be of one hour fire resistance.
- 15) It shall be ensured that the entire existing fire protection & fire-fighting system installed in the building as per CFO's NOC issued shall be kept in good working condition at all times.
- 16) **STRETCHER LIFT:**
 - a) The stretcher lift shall accommodate a twenty-four (24) inch by eighty-four (84) inch ambulance stretcher in the horizontal, open position and shall be identified by the international symbol for emergency medical services. (A hospital shaped elevator allowing the stretcher to roll straight into the elevator, which meets other handicap requirements, will be acceptable).
 - b) The symbol shall not be less than 3 inches (76 mm) high and shall be placed inside on both sides of the hoist way door frame.
 - c) In all structures four or more stories in height, at least one elevator shall be provided with a minimum clear distance between walls or between walls and door excluding return panels, of not less than 80" by 54", and a minimum distance from wall to return panel of not less than 51" with a 42" side slide door, unless otherwise designed to accommodate an ambulance type stretcher 84" by 24" in the horizontal position.
 - d) The 3500 pound capacity lifts provides an inside car dimension of 6'- 8" wide by 5'-3" deep and is provided with a 3'-6" center opening door. The inside car dimension will accommodate the stretcher, however, with this configuration; the stretcher must be tipped through the door opening which does not comply with code.

- e) Landing doors and lift car doors of the lifts shall be of steel shuttered with fire resistance of two hour. No collapsible shutter shall be permitted.
 - f) One hour FRD shall be provided to stretcher lift with the vision glass.
 - g) There shall be an alternate electric supply from a generator/separate substation of an adequate capacity apart from the electric supply of the building and the cables run in a route safe from fire i.e. within the lift shaft. In case of failure of normal electric supply, it shall automatically trip over to alternate supply.
 - h) The operation of the stretcher lift should be by a simple toggle or two button switch situated in glass-fronted box adjacent to the lift at the entrance level. When the switch is on, landing call points will become inoperative and the lift will be on car control only or on priority control device. When the switch is off, the lift will return to normal working. The lift can be used by the occupants in normal times.
 - i) The words 'stretcher lift' shall be conspicuously displayed in fluorescent paint on the lift landing doors at each floor level.
- 17) AUTOMATIC SPRINKLER SYSTEM:-**
Automatic sprinkler system shall be provided in the proposed lift lobbies on all floors as per relevant I.S specification.
- 18) AUTOMATIC SMOKE DETECTION AND FIRE ALARM SYSTEM:-**
Automatic smoke detection system with manual fire alarm system shall be provided in the electric meter room, in lift machine rooms & lift lobbies on all floors as per relevant I.S specification.
- 19) FIRE EXTINGUISHERS :-**
- a) One Dry Chemical Powder (A.B.C.) type fire extinguishers of 09 kgs. Capacity having B.I.S. certification mark each along with two sand buckets shall be kept in lift machine rooms, electric meter room etc.
 - b) One Dry Chemical Powder (A.B.C.) type fire extinguishers of 09 kgs. Capacity each having B.I.S. certification mark shall be kept at prominent place in every 100 sq.mtrs. on each floor of the building.
- 20)** Luminous/self-glowing 'Fire Exit', 'Way To Exit', staircase etc. pictorial signage's shall be provided at suitable locations showing the direction of escape.
- 21)** Smoking, cooking, dwelling & use of naked light shall be strictly prohibited under premises.
- 22)** Good housekeeping shall be maintained on the premises with proper ventilation.
- 23)** Portable light/install light shall be provided at strategic location in this commercial area premise.
- 24)** All the staff/employees & security guards on duty shall be trained about evacuation procedure & to communicate in case of emergency to the concern authority i.e. Police, Fire Brigade & also trained to use the fixed fire-fighting installation system of the premises & bldg. etc. and the use of portable fire extinguishers in the event of emergency.
- 25)** No changes except as stated above and as shown on the enclosed plans shall be carried out on the premises unless permitted by this department.
- 26)** The structural stability certificate from the competent authority shall be obtained before commencement of the proposed work & also after completion of work.
- 27) After the completion of above said work Licensed Surveyor should apply to this department for acquiring compliance certificate. If the party failed to get the Final Fire Safety Approval from this department this recommendation letter shall be treated as cancelled & further process shall not be permitted.**

- 28) Fire Brigade dept. reserves the right to change/alter/add/delete the terms and condition of these fire safety remarks as per the situation permits with prior intimation to the occupier
- 29) Electrical Audit and its compliance shall be done as per the rule.
- 30) This Fire safety requirement is issued from fire risk & life safety point of view only, and without prejudiced to any legal matter pending before court of law.
- 31) If any addition or alterations or extension in the Bldg. have to be carried out hereafter, same shall be strictly done with prior approval/permission & sanction of C.F.O. & other competent concerned authorities of MCGM to make the activity legalized and regularized.
- 32) Authenticity of the structure, area, premises & activity if any shall be verified by concern Municipal Authorities, till then further process shall not be permitted.
- 33) All civil engineering side shall be scrutinized, verify & confirm by the E.E.B.P.(E.S.) and necessary required permission/rules applicable shall be obtained from other concerned departments/authority to make the activity legalized and regularized.
- 34) If any matter in this case found violation of DCR-1991/DCPR 2034, then this proposal shall be referred back to this department for fresh fire safety remark.

The party has paid a scrutiny fee of Rs. 25,000/- vide online Challan No. CHE/CFO/159407/25, dated 13/01/2025. Party has also paid Fire Service fees of Rs. 23,104/- vide Challan No. CHE/CFO/159412/25, dated 13/01/2025 on the gross built-up area of 152.00 sq. mtrs. as certified by Architect vide area certificate dated 17/12/2024.

However, E.E.B.P.(E.S.) is requested to verify the total built-up area & inform this department, if the same is found to be more for the purpose of levying additional Scrutiny fees, if required.

With reference to Maharashtra Fire-Prevention & Life Safety Measure Act. 2006 (2007 of Mah-III) & Maharashtra Fire-Prevention & Life Safety Measure Act. Amended 2023 & Circular from the Directorate of Maharashtra Fire Services u/r. No. मअसे-2023-59/895, dated 02/06/2023, Fire & Emergency fees is applicable from 30/05/2023. In this regards, as per B.R.C. No. 78, dated 15/03/2024 & letter MFS/51/2024/481, dated 11.03.2024 regarding guidelines for calculating Fire & Emergency Service fees from Director, Maharashtra Fire Services & Architect/Licensed Surveyor/Developer/Owner has submitted letter along-with Undertaking from Developer/Owner regarding assurance that, if necessary, modification as proposed in Rule 19 of Maharashtra Fire Prevention & Life Safety Measure Rule, 2009 is not carried out in the revised rules by Directorate, Maharashtra Fire Services then Additional Fire Service Fees if any levied if necessary will be paid as demanded by Mumbai Fire Brigade vide new circular/notification in future. Hence Architect/Licensed Surveyor/Developer shall pay the necessary fees as per the demand note from this office, as & when demanded in the future.

**Divisional Fire Officer
(Scrutinized & Proposed by)**

**Dy. Chief Fire Officer
(Verified & Approval by)**

Copy to:

1. E.E.B.P.(E.S.).

2. Architect, Mr. B. H. Wadhwa of M/s. B. H. Wadhwa & Co.

